

**GOVERNMENT OF GOA
QUALITY CONTROL LABORATORY
WATER RESOURCES DEPARTMENT**

Test Report No.: WRD/Q.C./F.6-3/Soil. T- 1479 & 1480 /Lab/ 127 /2020-21/ Dated: 04 / 11/2020.

Laboratory: Bicholim

Sub Division: V (QC)/WRD/Bicholim

Sub.: Improvement to the inspection path from ch. 12.400 kms to ch. 16.100 kms of RBMC of TIP at Village sarvernem Ozarim and Nagzar in Pernem Taluka

Ref to requisition No.: F.361/SDI/WDVII/WRD/2020-21/141 DATED: 12/10/2020

Qty. Received: 1 bag each. **Date of Receipt:** 16/10/2020 **Tested on:** 27/10/2020 & 02/11/2020 **Ref to IS/CPWD Specification:** IS: 2720, Part V, 1985

Sample of: Soil

O.S. No. : 4181 &4182/SS

Lab. Sample No.:9452.

Tested by: Mrs. S.B. Naik Shirodkar ,J.E

REPORT

Sr. No.	Description of sample	Tested for	Results	Max./Min. value permissible	Remarks
1.	Soil: (L.S.No. 9452)	I) <u>Plasticity Index.</u>	Liquid Limit :- 30.77 % Plastic Limit :- 25.70 % Plasticity Index :- 5.07		

Copy to: 1. The Assistant Engineer, SDI, WDVII,WRD, Dhargal, Pernem – Goa.

2. Copy Submitted to The Superintending Engineer, CPO, WRD, Porvorim – Goa for kind information.

3. Copy Submitted to The Executive Engineer, W.D.VII, WRD, Dhargal,Pernem – Goa.

4. Q.C. Lab file

5. Bill File.

Junior Engineer

Assistant Engineer